

PROCEEDINGS

OF THE Chief Conservator of Forests, Trivandrum

Sub:- Schedule of rates –stacking charges.

Read :- 1. Data item item 4a to 4c and 5a to 5b.

2. Letter No. Metric 2776/69/29.5.70.

Order No. D3 (L. Dis) 12733/70 dt. 26.6.70.

The P.W.D. data items 4a to 4c and 5a to 5b dealing with the items of uprooting the stumps of trees contains the work ‘stacking the serviceable materials’. Usually the uprooted stumps are not got stacked. In future all such materials should be got stocked during execution of that item of work and the details of stack measurement should be recorded in the receipt column of the measurement book.

The Chief Engineer who was requested to fix a rate towards the stacking charges of stumps for recovery in cases where the stacking is not done, has replied that the data for such minute items can be done by the officer concerned using his discretion based on actual observations.

As such the data provision of 0.6 man item 5.b of the standard data has been disturbed as follows for future guidance of the officers dealing with such item of works.

Item 5.b of standard data Uprooting and removing only stumps of trees of all girths than palmyrah or coconut including stacking. 0.6 man.

Distributed as

- | | |
|--|----------|
| 1. Removing earth for facilitating the cutting and separating of stumps. | 0.2 man. |
| 2. Cutting and separating the stumps | 0.3 man |
| 3. Removing and stacking the serviceable materials. | 0.1 man |

A copy of Chief Engineer’s No. Metric/2776/69/29-5-70 is also enclosed.

Sd /- Chief Conservator of Forests

Endt . D.5915/68 dt. 9.7.70.

Copy to schedule of rates, date book and sections ML, CH, TR, KT and stock file.

For Conservator of Forests,
Trichur